



CLIENT: SCOTT RENEWABLES

Nacelle Housing and Gearbox Mount



Francis Brown Ltd

Project Overview

Francis Brown Limited was contracted to provide procurement of all materials, manufacturing, inspection, project management, delivery and engineering services to Scott Renewables to ensure safe and satisfactory completion of the project.



Statistics:



Location:
Emec, Orkney
Islands



**14 colleagues
involved**



Materials:
1. S355 J2+N.



Delivery time:
12 weeks



Size: 3 metre x 3 metre
x 2.6 metre



**Accident/incident
free throughout**



Total weight:
19 Tonne

Francis Brown Scope of Work

- Full fabrication/machining of all items
- Full inspection of all items throughout fabrication using our FARO Laser System
- Surface treatment and painting
- Co-ordination of equipment transportation
- Project management throughout the scheme
- Supply of full documentation pack in a timely manner.

Project Outcome

Francis Brown Limited provided several project specific solutions to enable an efficient equipment fabrication, machining, assembly and delivery to Scott Renewables.